



TOWN OF PERINTON

1350 TURK HILL ROAD, FAIRPORT, NEW YORK 14450-8796
(585) 223-0770, Fax: (585) 223-3629, www.perinton.org


Parking Lot Striping Requirements

208-16. Off-street parking and loading. [Amended 10-13-1977 by L.L. No. 7-1977; 5-9-1990 by L.L. No. 3-1990]

In all districts there shall be provided, at the time any building or structure is erected, enlarged, increased in capacity or changed in use, improved and usable parking spaces for automobiles in accordance with the requirements of this section.

A. General conditions.

- (1) Each off-street parking space for any use shall measure a minimum of 9 feet by 18 feet and shall be designed with twenty-four-foot travel aisles for two-way travel or fifteen-foot travel aisles for one-way travel.
- (2) All paved parking areas, with the exception of those related to one-family and two-family dwellings, shall be hairpin striped in the following manner:
 - (a) Striping shall be yellow or white, three inches to four inches in width, outside dimension of the double stripe 12 inches. The area between each set of double stripes shall be eight feet minimum.
 - (b) Handicapped parking spaces shall be provided in an area and location in accordance with the New York State Uniform Fire Prevention and Building Code.



Signage. Each accessible parking space shall be provided with signage displaying the international symbol of accessibility and read "Permit Required". Each access aisle shall be provided with signage reading "No Parking Anytime." Signs shall be permanently installed at a clear height of between 60 inches (1525 mm) and 84 inches (2185 mm) above grade and shall not interfere with an accessible route from an access aisle.